

TUDELU, LLC ACOUSTICAL PERFORMANCE TEST REPORT

SCOPE OF WORK

ASTM E90 SOUND TRANSMISSION LOSS TESTING ON
TUDELU PRIVATE, ACOUSTICAL PANELS

REPORT NUMBER

P3024.04-113-11-R1

TEST DATE

01/23/23

ISSUE DATE

02/22/23

REVISION 1 DATE

03/23/23


PAGES

10

DOCUMENT CONTROL NUMBER

RT-R-AMER-Test-2761 (09/09/22)

© 2017 INTERTEK



TEST REPORT FOR TUDELU, LLC

Report No.: P3024.04-113-11-R1

Revision 1 Date: 03/23/23 Date: 02/22/23

REPORT ISSUED TO

TUDELU, LLC

100 Industrial Avenue #C
Little Ferry, New Jersey 07643

SECTION 1

SCOPE

Architectural Testing, Inc. (an Intertek company) dba Intertek Building & Construction (B&C) was contracted by Tudelu, LLC to conduct a sound transmission loss test. Results obtained are tested values and were secured by using the designated test methods. The complete test data is included herein. The client provided the test specimen. All measurements were conducted in the HT test chambers at Intertek B&C located in York, Pennsylvania.

This report does not constitute certification of this product nor an opinion or endorsement by this laboratory. Intertek B&C will service this report for the entire test record retention period. The test record retention period ends four years after the test date. Test records, such as detailed drawings, datasheets, representative samples of test specimens, or other pertinent project documentation, will be retained for the entire test record retention period.

Unless differently required, Intertek reports apply the "Simple Acceptance" rule, also called "Shared Risk approach," of ILAC-G8:09/2019, Guidelines on Decision Rules and Statements of Conformity.

For INTERTEK B&C:

COMPLETED BY:	Cody L. French	REVIEWED BY:	Kurt A. Golden
	Technician		Manager
TITLE:	Acoustical Testing	TITLE:	Acoustical Testing
SIGNATURE:		SIGNATURE:	
DATE:	03/23/23	DATE:	03/23/23

CLF:jmcs

This report is for the exclusive use of Intertek's Client and is provided pursuant to the agreement between Intertek and its Client. Intertek's responsibility and liability are limited to the terms and conditions of the agreement. Intertek assumes no liability to any party, other than to the Client in accordance with the agreement, for any loss, expense or damage occasioned by the use of this report. Only the Client is authorized to permit copying or distribution of this report and then only in its entirety. Any use of the Intertek name or one of its marks for the sale or advertisement of the tested material, product or service must first be approved in writing by Intertek. The observations and test results in this report are relevant only to the sample(s) tested. This report by itself does not imply that the material, product, or service is or has ever been under an Intertek certification program.



TEST REPORT FOR TUDELU, LLC

Report No.: P3024.04-113-11-R1

Revision 1 Date: 03/23/23 Date: 02/22/23

SECTION 2

SUMMARY OF TEST RESULTS

SERIES/MODEL	Tudelu Private
TYPE	Acoustical panels
DESCRIPTION	Tudelu Private Panel (3 mm vinyl material) 4" Air space Tudelu Private Panel (3 mm vinyl material)
DATA FILE NO.	P3024.03A
STC	36
OITC	22

SECTION 3

TEST METHODS

The specimens were evaluated in accordance with the following:

ASTM E90-09 (2016), *Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions and Elements*

ASTM E413-22, *Classification for Rating Sound Insulation*

ASTM E1332-22, *Standard Classification for Rating Outdoor-Indoor Sound Attenuation*

ASTM E2235-04 (2020), *Standard Test Method for Determination of Decay Rates for Use in Sound Insulation Test Methods*

SECTION 4

SPECIMEN INSTALLATION

A sound transmission loss test was initially performed on a filler wall.

The specimen plug was removed from the filler wall assembly. The specimen was placed on an isolation pad in the test opening. Duct seal was used to seal the perimeter of the specimen to the test opening on both sides. The interior side of the specimen, when installed, was approximately 1/4" from being flush with the receive room side of the filler wall. A stethoscope was used to check for any abnormal air leaks around the test specimen prior to testing. Operable portions of the test specimen, if any, were cycled at least five times prior to testing.

TEST REPORT FOR TUDELU, LLC

Report No.: P3024.04-113-11-R1

Revision 1 Date: 03/23/23 Date: 02/22/23

**SECTION 5
EQUIPMENT**

The equipment listed below meets the requirements of the test methods stated in Section 3 of this report.

INSTRUMENT	MANUFACTURER	MODEL	DESCRIPTION	ASSET #	CAL DATE
2-Channel Analog Input	National Instruments	NI-9250	2-Channel Analog Input	INTO2580	03/22
2-Channel Analog Input	National Instruments	NI-9250	2-Channel Analog Input	INTO2581	03/22
2-Channel Analog Input	National Instruments	NI-9250	2-Channel Analog Input	INTO2581	03/22
2-Channel Analog Input	National Instruments	NI-9250	2-Channel Analog Input	INTO2583	03/22
2-Channel Analog Input	National Instruments	NI-9250	2-Channel Analog Input	INTO2584	03/22
2-Channel Analog Input	National Instruments	NI-9250	2-Channel Analog Input	INTO2585	03/22
Source Room Microphone	National Instruments	378C20	Microphone and Preamplifier	INTO2910	02/22
Source Room Microphone	PCB Piezotronics	378C20	Microphone and Preamplifier	INTO2911	02/22
Source Room Microphone	PCB Piezotronics	378B20	Microphone and Preamplifier	64340	10/22
Source Room Microphone	PCB Piezotronics	378C20	Microphone and Preamplifier	INTO2427	02/22
Source Room Microphone	PCB Piezotronics	378C20	Microphone and Preamplifier	INTO1089	02/22
Receive Room Microphone	PCB piezotronics	378C20	Microphone and Preamplifier	INTO2912	02/22
Receive Room Microphone	PBC Piezotronics	378B20	Microphone and Preamplifier	64902	10/22
Receive Room Microphone	PCB Piezotronics	378B20	Microphone and Preamplifier	64903	08/22
Receive Room Microphone	PCB Piezotronics	378B20	Microphone and Preamplifier	64910	02/22
Receive Room Microphone	PCB Piezotronics	378B20	Microphone and Preamplifier	64911	10/22
Receive Room Environmental Indicator	Comet	T7510	Receive Room	64915	02/22
Source Room Environmental Indicator	Comet	T7510	Source Room	64914	03/22
Microphone Calibrator	Norsonic	1251	Acoustical Calibrator	Y002919	04/22

*- Note: The calibration frequency for this equipment is every two years per the manufacturer's recommendation.

TEST CHAMBER

	VOLUME	DESCRIPTION
RECEIVE ROOM	234 m ³	Rotating vane and stationary diffusers Temperature and humidity controlled Isolation pads under the floor
SOURCE ROOM	207 m ³	Stationary diffusers only Temperature and humidity controlled

	MAXIMUM SIZE	DESCRIPTION
TL TEST OPENING	4.27 m wide by 3.05 m high	Vibration break between source and receive rooms

TEST REPORT FOR TUDELU, LLC

Report No.: P3024.04-113-11-R1

Revision 1 Date: 03/23/23 Date: 02/22/23

SECTION 6

LIST OF OFFICIAL OBSERVERS

NAME	COMPANY
Yanky Fleischman	Tudelu, LLC
Cody L. French	Intertek B&C

SECTION 7

TEST PROCEDURE

The sensitivity of the microphones was checked before measurements were conducted.

The transmission loss values were obtained for a single direction of measurement.

Two background noise sound pressure level and five sound absorption measurements were conducted at each of five microphone positions.

Two sound pressure level measurements were made simultaneously in receive and source rooms at each of five microphone positions.

The air temperature and relative humidity conditions were monitored and recorded during all measurements.

Data for flanking limit tests, repeatability measurements, and reference specimen tests are available upon request.

Intertek B&C will store samples of test specimens for four years.

SECTION 8

ACOUSTICAL TEST CALCULATIONS

Transmission loss (TL) at each 1/3 octave frequency is the average source room sound pressure level minus the average receive room sound pressure level, plus, 10 times the log of the specimen area divided by the sound absorption of the receive room with the sample in place.

STC Rating

To obtain the Sound Transmission Class (STC), read the TL of the contour curve at 500 Hz. The sum of the deficiencies below the contour curve must not exceed 32. The maximum deficiency at any one frequency must not exceed 8.

OITC Rating

The Outdoor-Indoor Transmission Class (OITC) is calculated by subtracting the logarithmic summation of the TL values from the logarithmic summation of the A-weighted transportation noise spectrum stated in ASTM E1332.

TEST REPORT FOR TUDELU, LLC

Report No.: P3024.04-113-11-R1

Revision 1 Date: 03/23/23 Date: 02/22/23

SECTION 9

SPECIMEN DESCRIPTION

Tudelu Private acoustical panels consisted of one 48" by 72" frame constructed with 1-1/2" thick by 4" wide wood lumber and fastened together with screws. One layer of mass loaded vinyl was screwed to the wood frame on both sides, creating the 4" air space.

MEASURED MASS VINYL WEIGHT (lbs/ft ²)	PANEL TOTAL WEIGHT (lbs)	PANEL AVERAGE WEIGHT (lbs/ft ²)
1.070	74	3.08

Photographs are included in Section 11.

The client did not supply a report drawing of the test specimen.

TEST REPORT FOR TUDELU, LLC

Report No.: P3024.04-113-11-R1

Revision 1 Date: 03/23/23 Date: 02/22/23

SECTION 10

TEST RESULTS

P3024.03A DATA

SPECIMEN AREA	2.23 m ²	RECEIVE TEMP.	22.1 °C	SOURCE TEMP.	22.2 °C
TECHNICIAN	Cody L. French	RECEIVE HUMIDITY	50%	SOURCE HUMIDITY	52%

FREQ (Hz)	BACKGROUND SPL (dB)	ABSORPTION (m ²)	SOURCE SPL (dB)	RECEIVE SPL (dB)	SPECIMEN TL (dB)	95% SAMPLING LIMIT	NUMBER OF DEFICIENCIES
80	37.4	6.4	105	94	7	2.67	-
100	30.7	6.7	105	89	12	2.06	-
125	35.5	5.8	107	87	15	1.14	5
160	38.4	5.1	107	88	16	1.22	7
200	35.9	5.9	107	82	21	0.83	5
250	29.7	6.0	104	72	27	0.47	2
315	24.3	5.8	104	72	28	0.69	4
400	21.9	5.7	103	66	33	0.55	2
500	18.5	5.6	104	65	34	0.38	2
630	16.9	5.7	103	63	36	0.24	1
800	14.9	6.1	102	59	38	0.27	0
1000	10.4	6.2	103	57	42	0.26	0
1250	9.0	6.8	102	52	46	0.21	0
1600	6.8	7.1	101	47	49	0.15	0
2000	6.1	7.6	102	42	55	0.23	0
2500	6.1	8.7	102	38	58	0.23	0
3150	6.9	10.4	101	33	61	0.20	0
4000	9.7	12.9	99	27	65	0.23	0
5000	11.6	16.3	99	23	68	0.40	-
STC RATING	36 (Sound Transmission Class)						
DEFICIENCIES	28 (Sum of Deficiencies)						
OITC RATING	22 (Outdoor-Indoor Transmission Class)						


- Notes:**
- 1) Receive Room levels less than 5 dB above the Background levels are red.
 - 2) Specimen TL levels listed in red indicate the lower limit of the transmission loss.
 - 3) Specimen TL levels listed in green indicate that there has been a filler wall correction applied

TEST REPORT FOR TUDELU, LLC

Report No.: P3024.04-113-11-R1

Revision 1 Date: 03/23/23 Date: 02/22/23

P3024.03A GRAPH



TEST REPORT FOR TUDELU, LLC

Report No.: P3024.04-113-11-R1

Revision 1 Date: 03/23/23 Date: 02/22/23

SECTION 11

PHOTOGRAPHS



Photo No. 1

Receive Room View of Installed Test Specimen



Photo No. 2

Source Room View of Installed Test Specimen



Total Quality. Assured.

130 Derry Court
York, Pennsylvania 17406

Telephone: 717-764-7700
Facsimile: 717-764-4129
www.intertek.com/building

TEST REPORT FOR TUDELU, LLC

Report No.: P3024.04-113-11-R1

Revision 1 Date: 03/23/23 Date: 02/22/23

SECTION 12

REVISION LOG

REVISION #	DATE	PAGES	REVISION
0	02/22/23	N/A	Original Report Issue
1	03/23/23	3, 6	Changed type to Acoustical Panels, Replaced product name to Private